

THE TABLES PRESENT THE RESULTS OF THE WORK CARRIED OUT IN THE KEY AREAS OF uST TECHNOLOGY

Table 1

STRING RAIL OVERPASS

FACILITY	CRITERION			
	Nomenclature of track structure types suitable for achieving the target speed characteristics of the complex	Total length of implemented transport complex lines of a particular type	Tested climatic zones of complex operation	Tested speed modes of complex operation (degree of achievement of target operating speed indicators)
uST rapid passenger complexes (maximum speed – 150 km/h, average operating speed – 70 km/h)	<ul style="list-style-type: none"> • uLite lightweight overpass (rail stressing – 60 tf, uPod weight – 1.6 tons) • Super-light track structure (rail stressing – 80 tf, uPod weight – 2 tons) • Semi-rigid track structure (rail stressing – 240 tf, uPod weight – 6 tons) • Flexible track structure (rail stressing – from 150 tf, uPod weight – 8 tons) • Truss track structure (rail stressing – 240 tf, uPod weight – 17 tons) • Semi-flexible heavy-duty overpass (rail stressing – 1,800 tf, maximum permissible uPod weight – up to 60 tons)* • Rigid heavy-duty string rail overpass (rail stressing – up to 1,400 tf, uPod weight – 60 tons)* • Rigid heavy-duty string rail overpass in tropical design (rail stressing – up to 1,800 tf, maximum permissible uPod weight – up to 60 tons)* • Track switches 	More than 7,000 m	<ul style="list-style-type: none"> • Moderate climate • Tropical climate 	70–110 km/h (target indicators of operating speed have been achieved at 100%)

<p>uST cargo complexes (maximum speed – 150 km/h, average operating speed – 40 km/h)</p>	<ul style="list-style-type: none"> • uLite lightweight overpass (rail stressing – 60 tf, uPod weight – 1.6 tons) • Super-light track structure (rail stressing – 80 tf, uPod weight – 2 tons) • Semi-rigid track structure (rail stressing – 240 tf, uPod weight – 6 tons) • Flexible track structure (rail stressing – from 150 tf, uPod weight – 8 tons) • Truss track structure (rail stressing – 240 tf, uPod weight – 17 tons) • Semi-flexible heavy-duty overpass (rail stressing – 1,800 tf, maximum permissible uPod weight – up to 60 tons)* • Rigid heavy-duty string rail overpass (rail stressing – up to 1,400 tf, uPod weight – 60 tons)* • Rigid heavy-duty string rail overpass in tropical design (rail stressing – up to 1,800 tf, maximum permissible uPod weight – up to 60 tons)* • Track switches 	<p>More than 7,000 m</p>	<ul style="list-style-type: none"> • Moderate climate • Tropical climate 	<p>40–70 km/h (target indicators of operating speed have been achieved at 100%)</p>
<p>uST 2-in-1 cargo and passenger complexes (maximum speed – 150 km/h, average operating speed – 60 km/h)</p>	<p>0 km. Truss track structure (rail stressing – 240 tf, uPod weight – 17 tons) is suitable for movement at speeds not exceeding 150 km/h</p>	<p>895 m</p>	<p>Moderate climate</p>	<p>80 km/h (target indicators of operating speed have been achieved at 100%)</p>

* The track is under construction. Parameters may change.

Table 2

ROLLING STOCK

FACILITY	CRITERION				
	Rolling stock model range (capacity/payload)	Autonomous range from the onboard energy storage (determined by customer requirements)	Implementation stage of the target nomenclature of rolling stock required for industry formation	Achieved test-mode performance of complexes (relative to target indicator)	Total vehicle mileage (for MTBF testing)
uST rapid passenger complexes (maximum speed – 150 km/h, average operating speed – 70 km/h)	<ul style="list-style-type: none"> • Unified running mock-up or mule • uBike (2 passengers) • uWind (2 passengers) • uLite (8 passengers) • uCar (4 to 18 passengers) • Bi-rail uBus (14 seats) • Quad-rail uBus (48 seats) • Karat uBus (up to 36 seats) • Self-propelled chassis for testing the active systems of the automated control system 	<ul style="list-style-type: none"> • 50 km • 100 km • 250 km • 40 km • 200 km • 250 km • 200 km • 250 km • 50 km 	100%	100%	More than 2 mln km

<p>uST cargo complexes (maximum speed — 150 km/h, average operating speed — 40 km/h)</p>	<ul style="list-style-type: none"> • uTrans (capacity — up to 100 mln t/year) • uTruck (1.7 tons) • Low-capacity uCont (4.3 tons) • uCont for 20- and 40-foot containers (30.5 tons), at the assembly stage • BiWind 	<ul style="list-style-type: none"> • External power supply • 70 km • 50 km • 20 km • 250 km 	<p>80%</p>	<p>50% (The system for transporting 20- and 40-foot shipping containers has not been tested)</p>	<p>More than 400,000 km</p>
<p>uST high-speed cargo and passenger complexes (maximum speed — 500 km/h, average operating speed — 400 km/h)</p>	<ul style="list-style-type: none"> • The prototype of the traction module as part of the mock-up of the high-speed vehicle (EcoTechnoPark, Maryina Gorka). Manufactured for testing the characteristics of the load-bearing system, running gear, and power supply system from the railhead at low speeds (up to 100 km/h) • The prototype of the passenger cabin as part of the mock-up of the high-speed vehicle (uSky Center, UAE). Manufactured for testing the cabin, ergonomics, boarding/disembarkation comfort, and multimedia functionality 	<p>100 km (at 60 km/h)</p>	<p>1%</p>	<p>1% (6-seater vehicles with a speed of up to 150 km/h are optimal for ensuring passenger flow on lines with up to 1 million passengers per year. To accommodate 100 million passengers per year, a system with higher-capacity rolling stock and higher speeds needs to be tested)</p>	<p>Less than 10,000 km at speeds up to 60 km/h (MTBF testing was not conducted due to infeasibility)</p>

Table 3

INFRASTRUCTURE AND SUPPORT SYSTEMS

FACILITY	CRITERION			
	Implemented prototypes of infrastructure facilities for the complexes	Part of the nomenclature of implemented facilities of the complex required for industry formation	Tested operating modes of the automated control system	Tested power supply systems
uST rapid passenger complexes (maximum speed – 150 km/h, average operating speed – 70 km/h)	<ul style="list-style-type: none"> • Closed-type passenger stations • Open-type passenger stations • Stops • Traction substations • Control rooms • Service and repair rooms 	100%	<ul style="list-style-type: none"> • Manned mode (dispatcher control) • Automated mode for single vehicle operation on the line • Automated mode for the operation of two or more vehicles on the line 	<ul style="list-style-type: none"> • Power supply from the onboard energy storage • Traction power supply
uST cargo complexes (maximum speed – 150 km/h, average operating speed – 40 km/h)	<ul style="list-style-type: none"> • Loading and unloading terminals • Traction substations • Control rooms • Repair shops 	100%	<ul style="list-style-type: none"> • Manned mode (dispatcher control) • Automated mode for single vehicle operation on the line • Automated mode for the operation of two or more vehicles on the line 	<ul style="list-style-type: none"> • Power supply from the onboard energy storage • Traction power supply

uST high-speed cargo and passenger complexes (maximum speed – 500 km/h, average operating speed – 400 km/h)

The open-type passenger station was used, designed for the urban suspended uST with a speed of up to 150 km/h

1% (design, engineering (development), manufacturing (construction), state examination, testing, and certification of high-speed (500 km/h) systems should be performed):

1) a range of high-speed uPods (rail-powered) – passenger, cargo, mixed-use, public, and family types, both single and in train sets;

2) a fundamentally new electrified high-speed string rail overpass (track rigidity and smoothness – unevenness up to 5 mm over a 50 m span, including under high-speed vehicle load);

3) a large number of «second-level» infrastructure facilities – stations and terminals combined with anchoring structures, cargo terminals and closed-type depots, traction substations for ensuring power supply at 500 km/h, high-speed track switches, automated control systems and special communication systems, control rooms for managing the high-speed flow of uPods in complexes over 20 km in length, and others.)

Testing is completely absent (completion – 0%)

Testing is completely absent (completion – 0%)

Table 4

COMMERCIAL ACTIVITIES AND CERTIFICATION

FACILITY	CRITERION				
	Experience in certifying complex components	Number of projects designed using a particular type of uST complexes	Number of projects using a particular type of uST complexes that will be implemented commercially in the near future	Number of projects using a particular type of complexes that are actively under development based on commercial agreements	Degree of implementation of a particular type of uST complexes as a commercial product, considering all elements, systems, and subsystems
uST rapid passenger complexes (maximum speed – 150 km/h, average operating speed – 70 km/h)	<ul style="list-style-type: none"> • Certification of vehicles • Certification of building structures (string rail overpass, buildings, and structures) • Commissioning of facilities 	More than 1,000	More than 100	More than 10	100%
uST cargo complexes (maximum speed – 150 km/h, average operating speed – 40 km/h)	<ul style="list-style-type: none"> • Certification of vehicles • Certification of building structures (string rail overpass, buildings, and structures) • Commissioning of facilities 	More than 500	More than 10	0	80% (there are no tested systems for transporting 20- and 40-foot containers)
uST high-speed cargo and passenger complexes (maximum speed – 500 km/h, average operating speed – 400 km/h)	No	More than 100	0	0	Less than 1%